Mobile 75 S

Electro-mechanical mobile lift with 7.5 t capacity per column





Application

☐ Repair and maintenance

Description:

- ☐ Each column is equipped with a 3 kW motor
- ☐ Sturdy column construction offering many possibilities
- ☐ Easy access to all kinds of maintenance jobs
- ☐ Self-carrying spindle with nut sets and safety nuts
- □ Obstruction system
- ☐ Electronic cable-free synchronization of columns during raising/lowering
- 4 identical columns, each with control unit with alarm signal
- ☐ Lockable main switch for emergency stop on each column
- □ Different programs for operation of all columns, of two, etc.
- Connecting cables between columns inclusive in delivery
- ☐ Integrated towing jack on each column
- □ Hydraulically adjusted wheel with locking device on column back, which lowers towing jack automatically at approx. 600 kg load

All wheel sizes:

- □ ø800-1140 mm
- □ Fork length 290 mm

Standard colours:

- □ Columns: RAL 7016 grey
- ☐ Forks: RAL 3020 red

Versions:

- ☐ Available with 400 V / 3 phases, 50 cycles
- □ Cable versions:
 With 2 columns (15 t),
 4 columns (30 t),
 6 columns (45 t) or
 8 columns (60 t)

Optional extras:

- ☐ Support stand, 880-1410 mm, 8.2 t
- ☐ Support stand, 1350-2130 mm, 8.2 t
- ☐ Wheel adaptor 800-575 mm

Other optional extras and special colours available on request!





Scan the QR-Code for detailed product information.

Further Information on www.autopstenhoj.com

autop Maschinenbau GmbH

Sandkampstraße 90 D-48432 Rheine

- **4** +49 5971 8602-02
- +49 5971 8602-25
 info@autopstenhoj.com

STENHØJ A/S

Barrit Langgade 188-190 DK-7150 Barrit

- **** +45 76 82 13 30

Technical data	
Lifting capacity	7,500 kg
Lifting height	1,720 mm
Wheel distance	620 mm
Stroke length	1,605 mm
Lifting / lowering time	150 sec.
Motor	3 kW/column
Operation	electro-mechanical
Voltage	3 x 380/415 V – 50 Hz – 16 A
Min. height	115 mm
Total height	2,430 mm











